



ANSI/ASME ARTICULATING CRANE INSPECTION CONSISTS OF:

- PERFORMING ALL TASKS ON THE INSPECTION SHEET FOR AN ARTICULATING CRANE.
- TEST THE UNIT AND CHECK FOR ANY REPAIRS THAT IT MAY NEED.
- LOAD TESTING EACH HYDRAULIC CYLINDER AND HOLDING VALVE FOR PROPER OPERATION.
- LOAD TEST THE CRANE TO MAKE SURE THE OVERLOAD SAFETY SYSTEM WORKS AND IS ADJUSTED PROPERLY.
- CHECK ALL CRANE FUNCTION PRESSURES AND SYSTEM PRESSURE.
- CHECK THE TIMING OF THE CRANE TO MAKE SURE IT IS MANUALLY & REMOTELY WORKING PROPERLY.
- REMOVE PUMP FROM THE PTO AND INSPECT THE SPLINES ON BOTH. CLEAN AND GREASE THE SPLINES & REINSTALL.
- FLOW-TEST THE CRANE'S PUMP TO MAKE SURE OF PROPER OPERATION.
- TORQUE ALL MOUNTING AND ATTACHING HARDWARE ON THE CRANE.
- CHANGE ALL HYDRAULIC FILTERS AND INSPECT HYDRAULIC FLUID CONDITION.
- REMOVE ALL GREASE FROM THE HYDRAULIC EXTENDS, OUTRIGGERS AND THE UNIT.
- STEAM-CLEAN THE ENTIRE UNIT.
- INSPECT CRANE FOR ANY STRUCTURAL DAMAGE OR CRACKS.
- GREASE ALL PIVET POINTS, HYDRAULIC EXTENDS AND OUTRIGGERS.
- INSPECT TRUCK BODY FOR ANY CRACKS, TIE DOWNS THAT MAY BE LOOSE AND ALL BODY LIGHTS FOR PROPER OPERATION.
- FINAL TEST THE UNIT AND TOP OF HYDRAULIC OIL IF NEEDED.
- INSTALL A CERTIFIED INSPECTION STICKER ON THE CRANE, FOR THE ANNUAL INSPECTION.
- **WE ALSO HAVE A FREE PICK UP AND DELIVERY SERVICE.**

The above inspection will take between 5-7 hours to complete. In the event additional work is need to your unit. Telford Fifty-Five Enterprises will notify you immediately of the repairs needed and quote you on a time and material basis. No repairs will be made until we have received a signed repair quote from you the customer.

CONTACTS:

- Dan Sullivan Jr., Regional Sales Rep (Ph# 215-622-5499)
- TJ Smith, Parts Manager (Ph# 215-723-6771 / Fax# 215-723-0853)
- Tom Smith, Service Manager (Ph# 215-723-6771 / Fax# 215-723-0853)